

TO:
Shri/Smt.KRISHI INFRATECH
1-1
MAIN ROAD
SOMPETA

Sir/Madam,

Sub: APEPDCL - Intimation of Charges to be paid - Regd.

Ref: 1.Your application registration No.NSCREG03994856.
2.Estimate Sanction No.PAS-SDR No.S0303/2026-27 (Estimate No.SOM-1-01041).

In pursuance to your application registered under reference 1st cited above, an estimate was prepared and sanctioned by the competent Authority as per the rules in vogue. Based on the sanctioned estimate under reference 2nd cited, the following charges are to be paid for taking further action.

Application Fee:	Rs.	0.00
Service Line Charges:	Rs.	21,800.00
Development Charges:	Rs.	0.00
Security deposit:	Rs.	8,800.00
Service Connection Charges:	Rs.	0.00
Security Deposit for Layout:	Rs.	0.00
Additional Security Deposit:	Rs.	26,400.00
Advance CC Charges:	Rs.	0.00
Turnkey Charges:	Rs.	0.00
Urgency Charges:	Rs.	0.00

Total: Rs. 57,000.00

(Rupees fifty seven thousand only)

Hence, you are requested to pay the above charges by Online through APEPDCL Website i.e. <https://onlineapp.aeasternpower.com> (Or) in the form of Demand Draft (DD) in favour of "EXECUTIVE ENGINEER/OPERATION/APEPDCL/PALASA" payable at PALASA and furnish the same at AA0/ERO/APEPDCL/ERO-PALASA in advance, for taking further course of action against your application registered under reference 1st cited subject to the following conditions.

(1)The charges indicated above are only tentative and the applicant shall pay, in addition to above charges, leviable by the APEPDCL, in the context of above charges have become insufficient on whatsoever reason to provide electrical infrastructure to the applicant.

(2)If the applicant fails to pay the charges mentioned above on or before 11.11.2026 the APEPDCL shall reject the application without any further notice.

(3)In case, the applicant fails to avail supply within three (3) months from the date of issue of a separate notice under clause 5.9.2.1 of GTCS, the applicant shall pay the monthly charges communicated by the APEPDCL as per prevailing Tariff Order.

(4)The applicant shall pay Rs.50/- for revision of estimate.

(5)The prospective consumer are required to lay the service connection cable and also fix up the meter box and MCB (Cut-out) as per the standards and procedures prescribed in the GTCS.

DEPUTY EXECUTIVE ENGINEER
OPERATION, SOMPETA

This intimation letter is generated by System and needs no signature

Sir/Madam,

Detailed Estimation:

SNO	Data	Data/Features	Amount in Rs
1	01	Erection of 796 Mts 11KV Line on proposed 9.1 Mts PSCC Poles with 55Sqmm AAAC	578,734.00
2	02	Erection of 3ph 25KVA DTR	216,806.00
3	03	Release of 11KW Commercial Load with 3ph 5-30A IRDA Meter	2,722.00
Estimation Cost(Gross):			798,262.00
Estimation Cost(Net):			798,262.00
Total Estimation Cost(Gross):			798,262.00
Total estimation Cost(Net):			798,262.00

DATA 01: Erection of 796 Mts 11KV Line on proposed 9.1 Mts PSCC Poles with 55Sqmm AAAC

SNO	Mat.Code	Material Description	Quantity	Rate	UOM	Amount in Rs.
1	PLS00004	9.1MTS 280KGS PSCC POLES	22.000	3884.56	EA	85460.32
2	PLS00002	8MTS 200KGS PSCC POLES	6.000	2572.40	EA	15434.40
3	CDR00003	AAA CONDUCTOR 55 SQMM	2500.000	53.09	M	132725.00
4	FBR10002	11KV V X ARMS WITH MSCHANNEL 75X40	19.000	935.74	EA	17779.06
5	FBR10007	11KV TOP CLEAT WITH CLAMPS	19.000	374.06	EA	7107.14
6	FBR10004	11KV TAPPING CROSS ARMS	8.000	869.66	EA	6957.28
7	FBR10005	11KV SIDE ARMS WITH STUT	2.000	1886.82	EA	3773.64
8	FBR00004	M.S.STAY CLAMPS FOR 9.1 M PSCC POLES	6.000	279.66	EA	1677.96
9	FBR00002	M.S.BACK CLAMPS FOR 9.1 M PSCC POLES	29.000	133.34	EA	3866.86
10	FBR00003	M.S.STAY CLAMPS FOR 8 M PSCC POLES	6.000	108.56	EA	651.36
11	BNT00005	MS BOLTS AND NUTS 5/8X4"	10.000	103.26	KG	1032.60
12	HWR00002	11KV METAL PARTS (C and T)	24.000	129.80	EA	3115.20
13	INS10003	11KV POLYMER INSULATORS (C AND T)	24.000	354.00	EA	8496.00
14	INS10011	11KV POLYMER PIN INSULATOR WITH GIPIN	81.000	384.00	EA	31104.00
Sub Total:						319181.00
S&H Charges:						9575.00
Contingencies:						9575.00
Labour&Transport:						184000.00
Establishment&General Charges:						56403.00
Total:						578734.00

DATA 02: Erection of 3ph 25KVA DTR

SNO	Mat.Code	Material Description	Quantity	Rate	UOM	Amount in Rs.
1	DTA30018	3PH 25KVA DISTRIBUTION TRANSFORMER	1.000	137360.00	EA	137360.00
2	ABS10016	11KV 200A TT AB SWITCH WITH POLYMER INSU	1.000	10546.84	EA	10546.84
3	FBG00010	25/16KVA DTR MOUNTING ARRAGMENT	1.000	2705.74	EA	2705.74
4	FBG00024	11KV T/T AB SWITCH MOUNTING ARRANGEMENT	1.000	2554.00	EA	2554.00
5	BNT00006	MS BOLTS AND NUTS 5/8X6"	5.000	100.50	KG	502.50
6	CBX00003	LT XLPE CABLE 1 CORE 95 SQMM	10.000	100.58	M	1005.80
7	EMT00003	CI EARTH PIPE 50MM DIA	3.000	3257.98	EA	9773.94
8	EMT00017	GI EARTH FLAT 25 MM X 3 MM	20.000	73.75	KG	1475.00
9	HGF10004	11KV HG FUSE SET WITH POLYMER INSULATORS	1.000	5436.26	EA	5436.26
10	HGF00001	LT HG FUSE SET WITH POLYMER INSULATORS	1.000	2069.72	EA	2069.72

Sub Total:	173430.00
S&H Charges:	5203.00
Contingencies:	5203.00
Labour&Transport:	12000.00
Establishment&General Charges:	20970.00
Total:	216806.00

DATA 03: Release of 11KW Commercial Load with 3ph 5-30A IRDA Meter						
SNo	Mat.Code	Material Description	Quantity	Rate	UOM	Amount in Rs.
1	MTE30020	3PH 5-30A IRDA PORT METER PP BOX	1.000	1848.00	EA	1848.00
Sub Total:						1848.00
S&H Charges:						55.00
Contingencies:						55.00
Labour&Transport:						500.00
Establishment&General Charges:						264.00
Total:						2722.00

Charges Calculation:

Particulars	Amount in Rs/-
Cost of the Estimate (Gross):	798,262.00
Less: DTR Cost Exemption :	216,806.00
Less: Meter Cost Exemption :	2,722.00
Less: Line Cost Exemption :	0.00
Application Fee :	100.00
Service Line Charges :	21,800.00
Development Charges :	0.00
Security Deposit :	8,800.00
Security Deposit for Layout :	0.00
Service Connection Charges :	0.00
Additional SD Charges :	26,400.00
Advance CC Charges :	0.00
Urgency Charges :	0.00
Turnkey Charges :	0.00
Total Charges :	57,100.00

List of Applicant:

S.No.	LT Reg.No	Reg.Date	Applicant Name	Phase	New Load	Category
001	NSCREG03994856	24.07.2026	KRISHI INFRATECH	3	11KW	II(A)(i)